

*Deep Foundation Institute 35th Annual Conference
Hollywood, California October 2010*

**HAMMER-GROUT PILES
FOR THE
BRONX-WHITESTONE BRIDGE**

Andrew J. Burns, PE



*Ameir Altaee, PhD, PE, Urkkada Technology Ltd.
Hemal Shah, PE, PMP, The Conti Group*

HAMMER-CAST-IN-PLACE PILES FOR THE BRONX-WHITESTONE BRIDGE

- *Background*
- *Subsurface Conditions*
- *Proposed Means & Methods*
- *Collaboration by Stakeholders*
- *Pre-Production Load Testing*
- *Production Results*

BRONX-WHITESTONE BRIDGE

- *Owned and operated by Tri-Borough Bridge and Tunnel Association (TBTA) – a division of the MTA*
- *Constructed in 1939*
- *Main span of 2,300 feet*
- *Carries 200,000 vehicles per day*
- *One of three bridges connecting The Bronx and Queens boroughs of New York City*

BRONX-WHITESTONE BRIDGE



REPLACEMENT OF BRONX APPROACH

- *General contract awarded to The Conti Group in January 2009*
- *Contract value \$192 million*
- *Contract duration 48 months*
- *Complete replacement of 1,800 feet of approach ramp*
- *Maintain traffic throughout duration*
- *Install new foundations and support around the existing approach ramp*
- *Avoid settlement of existing foundations*


MINI-PILE FOUNDATIONS

- *Mini-pile subcontract awarded to Intercoastal Foundations & Shoring*
- *Urkkada Technology hired as mini-pile design consultant to mini-pile subcontractor*
- *772 mini-piles*
- *Design loads from 120 to 150 US tons*
- *Anticipated minimum pile depth of 75 feet*
- *Perform 15 static axial compression load tests to 250% of design load*
- *Approximately 50% of mini-piles to be installed in restricted headroom as low as 15 feet*

SUBSURFACE CONDITIONS

- *Soil borings from the original bridge construction revealed varied soil conditions along the approach*
- *New soil borings were performed – 2 for each new bent – one on either side of the approach*

SUBSURFACE CONDITIONS




SUBSURFACE CONDITIONS

- *Bedrock at depths of 60 to 130 feet*
- *Thick layers of decomposed rock in some locations*
- *Glacial overburden - from Geotechnical Report:*

The glacial materials consist of dense to very dense stratified sand and gravel with boulders, cobbles, and silt, and clay. These strata are inter-bedded with fine-grained layers of very stiff to hard organic-rich silt and clay, dense fine sand and silt with varying amounts of gravel.

SUBSURFACE CONDITIONS



MINI-PILE DESIGN CHALLENGES

- *Owner's Engineer/Designer:*

Find a single deep foundation type that is reasonably suited to varying soil conditions and can be installed in low headroom condition

- *Sub-contractor:*

Find means and methods to drill efficiently through soils which normally call for different types of tooling

CONTRACT SPECIFICATIONS

- *Contractor design*
- *Follow the design methodology detailed in Geotechnical Report, including FHWA bond values:*

Table 5.6 Recommended Ultimate Ground/GROUT Bond Strength

Stratum	Material Type	Estimated Ultimate Bond Strength, (ksf)
Glacial Deposits	Sand and Silt	4.5
	Sand and Gravel	6.2
	Clay and Silt	3.3
Decomposed Rock	Composite	4.5-6.2

- *Means and methods to be capable of drilling through cobbles, boulders, and sound rock*

PROPOSED MEANS AND METHODS

- *Risks*

- *restricted headroom*
- *stringent settlement criteria of ¼ inch maximum – existing approach supported on spread footings*
- *schedule - large quantity of piles – how many rigs would be required?*
- *difficult soil conditions leading to*
 - 1. low productivity (long duration and high cost)*
 - 2. dispute over use of DHH*

PROPOSED MEANS AND METHODS

The contract specifications restricted the use of down-hole-hammer (DHH) to drilling of obstructions and sound rock.

The sub-contractor would be expected to drill with casing, rotary bits (e.g. roller bits), and water flush until an obstruction was encountered, “trip-out”, use a DHH to drill and extend the casing through the obstruction, “trip-out” again, and return to cased rotary drilling to the full depth.


The pile was then to be tremie-grouted and pressure grouted as the casing is withdrawn.



PROPOSED MEANS AND METHODS


- *Develop a single drilling method capable of drilling efficiently through the varied soil conditions.*
- *Take advantage of higher productivity of large fixed mast drill rigs, where possible, in order to reduce the need for a larger number of crews in order to meet the schedule.*
- *Eliminate the risk of obstruction claims by drilling with a down-hole-hammer (DHH) throughout the process.*
- *Reduce potential settlement by utilizing “true” reverse-circulation drill rods together with grouting through the DHH and bit.*

PROPOSED MEANS AND METHODS

In general, the proposed method is most similar to a traditional auger-cast-in-place pile








IMPORTANT FEATURE:
AIR ESCAPE HOLE
(PREVENTS PRESSURIZING GROUND
WHEN THE BIT PLUGS)


THIS FEATURE ALSO ALLOWS
THE HAMMER TO KEEP RUNNING
SO BIT WILL UNPLUG IT'S SELF



TAPERED HOLE FEATURE: THE BIT FACE HOLES ARE
SMALLER THAN THE CUTTINGS EVACUATION TUBE
ENSURING ROCKS THAT ENTER THE BIT TRAVEL FREELY



IMPORTANT DEBRIS REMOVAL FEATURE:
THE HOLES WHERE THE DEBRIS ENTER THE
BIT ARE RIMMED WITH CARBIDE BUTTONS
TO BRAKE OVERSIZE ROCKS






- ← Discharge
- ← Grout-Intake Swivel
- ← Rotary Drill Head
- ← Air-Intake Swivel
- ← 13-5/8" diam. RC rods






SECTION A
NTS



SECTION B
NTS



SECTION C
NTS

Mini Pile




Job Site Data:

Project name: TBTA BW 89
 Client: Conti Corp
 Contractor: Intercoastal
 Machine: TM20_25

Data for Pile No: tp9

DRILL DATE: 4/23/2009
 DRILL START: 1:29:40 PM
 DRILL END: 2:51:09 PM
 DRILL TIME: 01:21:29
 DRILL DEPTH: 66.8 ft

GROUT DATE: 4/23/2009
 GROUT START: 2:51:09 PM
 GROUT END: 3:16:22 PM
 GROUT TIME: 00:25:13
 TOTAL VOLUME: 4.10 yd³



Inc: 0 - 64 = 2 ft
 Inc: 66 = 2.8 ft

COLLABORATION BY STAKEHOLDERS

- *Owner: TBTA*
- *Owner's Engineer: PB/Sells*
- *Construction Manager and Resident Engineer:
GPI/Parsons*
- *General Contractor: The Conti Group*
- *Subcontractor: Intercoastal*
- *Subcontractor's Design Engineer: Urkkada*

CHALLENGES TO ACCEPTANCE

- *Would continuous use of the DHH lead to unacceptable settlement of the existing structure?*
- *Could grout quality be assured when placing the grout through the center tube of the RC rods and DHH bit?*
- *Could grout-ground design bond values be achieved and verified during load tests?*
- *Could the reinforcing be placed with sufficient control so as not to slough the sides of the drilled and grouted hole?*
- *Could the procedures be monitored, inspected and controlled so as to provide assurance of continued performance throughout the production pile installation?*

PRE-PRODUCTION LOAD TESTING

- *Pre-production load test program:*
 - *4 bents*
 - *a sacrificial test pile plus 4 sacrificial reaction piles at each of the 4 bents*
 - *strain gages installed in test piles at 5 depths of interest: full reinforcing, casing and bar, immediately below casing, mid-depth of bond zone, and pile tip*
 - *PIT testing of all test and reaction piles*
- *A successful pre-production load test on a sacrificial pile would be required at each bent prior to starting production at the given bent*


ADDITIONAL PRODUCTION QUALITY CONTROL





- *Pile Integrity Testing (PIT) to be performed on up to 5% of the production piles. Selection of these piles would be by PB/Sells.*
- *“Proof” static testing up to 2% of production piles to 200% of design load. Selection of these piles would be by PB/Sells.*

PRE-PRODUCTION LOAD TEST RESULTS


- *Successful load tests were performed at bents 8, 9, 11, and 12*
- *Acceptance based on the gross movement (Davisson Criteria) and creep (< 0.01 "/hour and 0.03 "/log cycle of time) during a 48-hour hold period at 100% of design load*
- *Test load was increased to 250% of design load (12-hour hold and < 0.01 "/hour) to verify the achieved grout-ground bond values*

SUBSURFACE CONDITIONS





SUBSURFACE CONDITIONS



RESULTS

- *Pre-production testing did not result in any changes to means & methods or design lengths*
- *Some modifications were made to bit geometry to reduce air loss into soil formation*
- *All load tests (pre-production and production “proof” testing) were successful*
- *Maximum measured settlement of existing bridge structure was 1/8 inch*
- *Production Rates:*
 - *5 piles per rig-shift in unlimited headroom*
 - *2+ piles per rig-shift in 20-ft headroom*
- *No claims for obstructions*
- *20% reduction (conservative) in piling costs compared to conventional methods*



ACKNOWLEDGEMENTS

- *Robert Sackaris and William Lozito of Intercoastal Foundations & Shoring*
- *Vincent Montanti, Carl Redmond, and Justine Tietjen of TBTA*
- *Jeffrey Balinski, Gary Crozier, and Brendan Scahill of GPI/Parsons*
- *Paul Nietzsche, Joe Wang, and John Bryson of PB/Sells*
- *William Picken, Gerard Maurer Nestor Martinez and Sean Blum of The Conti Group*
- *Art Holte of Holte Manufacturing*